CITY IMPROVEMENT WORKS, BANGALORE.

Notice dated 2nd February 1924.

Notice is hereby given that sealed tenders for constructing a row of shops in the rear of the New Market Frontage, Bangalore City, will be received in person by the Municipal Commissioner, at his office up to 1 P.M., on Saturday the 16th February 1924. An approximate schedule of quantities, which is subject to alteration is given below. The work should be completed within seven months from the date of contract bond, showing proportionate progress monthly.

2. The plans and detailed estimates specifications and conditions may be seen at the Office of the Special Engineer, Visvesvarapuram Extension, between 12 noon and 5 P.M. on office days.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items of work specified will be executed. Rates should be quoted only for the units shown in the schedule. Tenders quoting for units other than those in the subjoined schedule will be rejected. The rates should also be noted in words.

4. Each tender must be accompanied by a deposit of Rs. 1,000 (one thousand) in cash or currency notes, as earnest money and be superscribed "Tender for constructing a row of shops in the rear of the Front Block of the New General Market, Bangalore City" in default of which the tenders will be rejected.

5. The final acceptance of any tender rests with the Municipal Council, which does not bind itself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. The name of the successful competitor will be posted on the notice board of the Office of the Special Engineer in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. Within eight days of the order of acceptance of the tender, the approved tenderer will be required to execute the usual contract bond, depositing the earnest money as security in default of which, his tender will be considered cancelled and his earnest money forfeited without further reference to him.

8. On the final disposal of tenders, the earnest money on rejected tenders will be returned to such tenderers on their applying to the Commissioner in person or through their accredited agents.

Abstract of quantities.

No.	Items of work	Per	Quantity.	Rate
1	Earthwork excavation for foundation	C. yd.	607	
2	Filling with coarse sand for foundation including watering and ramming	C. ft.	4,018	
3	Laying surki concrete for foundation	"	4,547	
4	Stone masonry in chunnam mortar for foundations including bond stones	"	4,012	
5	Stone masonry in chunnam mortar for basement including bond stones	"	1,169	
6	Burnt stone slabs of 6" thick exposed parts 2 lines dressed and the rest roughly dressed.	S. ft.	3,958	
7	Superstructure, coursed hammer dressed stone masonry in chunnam mortar including bond stones.	C. ft.	4,632	
8	Stone pillars (8" x 8") and 8½' high including capitals, one line dressed including iron pinning, fixing, etc., complete.	Each	80	
9	Stone bressummers 8" x 8" in section one line dressed including hoisting fixing, etc., complete.	C. ft.	179	
10	Teakwood doors, pannelled with heavy teak frames, heavy iron fittings, two coats of painting, etc., complete as per specification.	S. ft.	1,248	
11	Teakwood ventilators with iron bars glazed, etc., complete as per specification.	"	253	
12	Steel joists including hoisting fixing and two coats of painting after scraping and cleaning complete.	Cwt.	138	
13	Jack arched terrace roofing including concrete two courses of flat tiles and chunnam plastering top and bottom.	Sqr.	44·16	
14	Roofing of burnt stone slabs 4" thick with close joints to verandah including eaves, with concrete of 4½" thick and two courses of flat tiles, chunnam plastering on top on cement pointing.	"	39·48	
15	Burnt brick masonry cornice at bottom including eaves of 2½ feet with a cement plastered face 9" thick with cement plastering.	R. ft.	430	
16	Flooring with Cuddapah slabs of 1½" thick over 3" concrete bed and cement pointing.	Sqr.	56·14	
17	First class wire cut brick in chunnam mortar partition wall of 9" thick	C. ft.	2,700	
18	Cement pointing	Sqr.	159·03	
19	Constructing brick in chunnam ordinary parapet wall of 4½" thick and 2' high including pillasters and cement plastering.	R. ft.	868	
20	Earthwork filling in basement including consolidation	C. yd.	170	
21	Constructing U shaped cement concrete drain with cement plastering and stone slabs on top of sides (as per details to be obtained in Special Engineer's Office.)	R. ft.	480	

C. VIJAYARANGAM NAIDU,
Special Engineer.